

ARTESANO GALLERIA

CAMPINAS - SÃO PAULO - Brasil



PROJEKTTYP

BAUJAHR
2022

KUNDE
ARTESANO GALLERIA
EMPREENHIMENTOS
IMOBILIARIOS

AUFTRAGNEHMER
HLF CONSTRUTORA

DESIGNER
ARTESANO GALLERIA

VERWANDTE PRODUKTE

Herausforderung

The architectural challenge was to integrate the retaining and boundary walls into a single system,

initially conceived in gabions.



During Construction



During Construcion 2

Lösung

The retaining walls were designed using a gravity gabion retaining system. The architectural boundary walls were defined with a maximum thickness of 50 cm. To stabilise the architectural walls with gabions, it was necessary to use an internal metal structure that

guarantees their stability, while the hexagonal mesh gabions enclose the filling material and provide the finish idealised by the architect. In all, the architectural walls will have a face area of more than 500,00 m²..



During Construcion 3



During Construcion 4



During Construcion 7



GOOGLE MAPS ÖFFNEN



GOOGLE EARTH ÖFFNEN